


COMPOSITE WHEELS FOR LUNAR MOBILITY



Joshua Chen
Natalie Mark
Zack Morrison
Jackie Yang

Outline

- Requirements
- Design
- Fabrication
- Assembly
- Test



REQUIREMENTS



Size, Mass, and Strength



- Size {
 - Diameter = 24 inch
 - Width = 6 inch
- Mass {
 - Total < 3 kg
- Strength {
 - Lateral load > 256 lbf
 - Rim Pull > 165 lb*ft
 - Spoke load > 412 lbf
 - Point load > 1058 psi

DESIGN






• • •

Research, Analysis, and Comparison

Previous Work



Our Concepts





Design Comparison in Weighted Matrix




CRITERIA	WEIGHT	Spiral	Single Curved Composite	2-Curved Composite	Tweel	Spring Spokes	Straight Spokes	Mesh
Mechanical Reliability	5	3	4	4	2	2	5	2
Strength	4	3	3	4	2	2	5	2
Weight	5	3	5	3	2	4	5	4
Ride Smoothness	2	4	3	3	5	2	2	5
Obstacle Performance	3	3	3	3	4	3	3	3
Stability	3	3	3	2	4	2	3	3
Wear Resistance/ Durability	3	3	3	4	2	2	4	2
Flexibility/ Ground Compatibility	4	3	2	2	5	4	1	5
Feasibility	4	2	5	4	1	2	4	2
WEIGHTED TOTAL		97	118	108	92	87	124	100




Final Design



Mold Design




Spoke Design



Grouser Design

- 36 Grousers
- 4 Layers (2 Carbon, 2 Kevlar)
- Grouser Height $\sim 0.5^*\text{Spacing}$
 - 0.75" Height, 2" Spacing





Grouser Thickness Test



Sample Detail

C: Carbon Fiber
K: Kevlar
0/90 +45




Test Results


- Rim pull calculated load: 165 lb

	Test #1	Test #2	Test #3	Test #4	Test #5
# of layers	3-Ply	3-Ply	4-Ply	4-Ply	5-Ply
Width	$\frac{3}{4}$ "	1"	$\frac{3}{4}$ "	1"	$\frac{3}{4}$ "
Test max load	170 lb	170 lb	390 lb	310 lb	> 470 lb
Real max load	167 lb	167 lb	381 lb	303 lb	> 459 lb

Exploded View



Mass Analysis



FABRICATION

• • •

Mold & Component

Foam Block

Machined


Sand &
Epoxy

Surface
Cleaning

Layup
Ready

Mold Fabrication

- Foam blocks were cut and glued together to make appropriate size for mold



Foam Block

Machined

Sand &
Epoxy

Surface
Cleaning

Layup
Ready

Mold Fabrication

- Foam mold blocks were machined by robot arm in NSH Highbay



Foam Block



Machined



Sand &
Epoxy




Surface
Cleaning



Layup
Ready

Mold Fabrication

- Each mold was sanded and epoxied two times to ensure smooth and sealed surfaces for layup



Foam Block

Machined

Sand &
Epoxy

Surface
Cleaning

Layup
Ready

Mold Fabrication

- Clean and seal each mold multiple times to further ensure separation from mold after layup



Foam Block



Machined



Sand &
Epoxy



Surface
Cleaning



Layup
Ready

Mold Fabrication

- Mold is ready for composite layup



Material
Trimmed


Epoxy Covered

Pattern Layup

Pack & Cured

Composite Layup

- Strips of carbon fiber & Kevlar were cut to size



Material Trimmed

Epoxy Covered

Pattern Layup

Pack & Cured

Composite Layup

- Carbon & Kevlar strips were covered in epoxy resin



Material Trimmed

Epoxy Covered

Pattern Layup

Pack & Cured

Composite Layup

- Carbon & Kevlar strips are laid into place over mold



Material Trimmed

Epoxy Covered

Pattern Layup

Pack & Cured

Composite Layup

- Pack everything into vacuum bag and cure it for 8 hours in oven, then trim the parts into appropriate final shape



ASSEMBLY

• • •

Component & Wheel

Spokes




Grouasers



Rim + Grousers



Wheel



TEST

• • •


Lateral Load, Rim Pull, Spoke Load, and Point Load

Strength Test




Lateral Load

$1140 \text{ N} = 256 \text{ lbf}$





Rim Pull

$735 \text{ N} = 165 \text{ lbf}$




Spoke Load

$$2.5^*(\text{static}) = 1837 \text{ N} = 413 \text{ lbf}$$



Point Load

1058 psi



Impact Area = 0.11 in²



CONCLUSION

• • •

Requirements Check & Future Work

Requirements

Size Diameter = 24 inch

Width = 6 inch

Mass Total < 3 kg

2.166 kg = 28% ↓

Strength Lateral load > 256 lbf

Rim Pull > 165 lb*ft


Spoke load > 412 lbf


Point load > 1058 psi



Future Work

- Improve attachment between spoke & rim
- New mold with new foam
- Trim spokes w/o vibration
- Fabrication of 3rd & 4th wheel
- Attachment to rover
- Field testing





Q & A

• • •

Special Thanks

Wennie

John

Steve

Robert

Jessica